



# **REQUEST FOR PROPOSAL**

Date: 13 December 2021

Reference: RFP CO-21-0034SVP

1. The Philippine Institute of Traditional and Alternative Health Care (PITAHC) through its Bids and Awards Committee (BAC) invites interested bidders to submit a proposal, with the total Approved Budget for the Contract (ABC) in the total amount of Six Hundred Twenty-Four Thousand Five Hundred Eighty Pesos Only (PhP624,580.00) inclusive of VAT for the procurement of the item/s stated below:

| PITAHC<br>2021 APP<br>Ref     | PR<br>Number | Item Description   |
|-------------------------------|--------------|--|
| 5060404001<br>/<br>5021304000 | 21-06-0082   | SUPPLY, DELIVERY, INSTALLATION, TESTING AND<br>COMMISSIONING OF VARIOUS REQUIREMENTS FOR THE<br>PITAHC CENTRAL OFFICE LABORATORY |

| Lot<br>No | Item<br>No. | Item Description   | Estimated Cost | Total ABC per Lot |
|-----------|-------------|--|----------------|-------------------|
| 1         | 1           | Supply, Delivery, Installation, Testing,<br>and Commissioning of 1.5 HP Split-Type<br>Wall Mounted Air Conditioning Units  | PhP272,800.00  | PhP431,200.00     |
|           | 2           | Supply, Delivery, Installation, Testing, and<br>Commissioning of 2.0 HP Split-Type Wall<br>Mounted Air Conditioning Units: | PhP158,400.00  |                   |
| 2         | 1           | Supply Delivery, Installation, and Testing of<br>2x28W LED Louver Housing, Recessed<br>Lighting Fixtures                   | PhP86,130.00   | PhP125,730.00     |
|           | 2           | Supply, Delivery, Installation, Testing, and<br>Commissioning of Exhaust Fans with Ducting                                 | PhP26,400.00   |                   |
|           | 3           | Supply, Delivery, Installation, and Testing of<br>LED Emergency Light  | PhP13,200.00   |                   |
| 3         | 1           | Supply, Delivery, Installation, Testing, and<br>Commissioning of Smoke Detectors   | PhP19,800.00   | Php67,650.00      |
|           | 2           | Supply and Delivery of Room Thermometers   | PhP16,500.00   |                   |
|           | 3           | Supply and Delivery of Fire Extinguishers  | PhP23,100.00   |                   |
|           | 4           | Supply and Delivery of Waste Bins  | PhP8,250.00    |                   |

- 2. Procurement shall be conducted through Small Value Procurement under Section 53.9 Negotiated Procurement as prescribed under Rule XVI- Alternative Methods of Procurement of the 2016 Revised Implementing Rules and Regulations (IRR) of Republic Act (R.A.) No. 9184, otherwise known as the "Government Procurement Reform Act".
- The proposal must be duly signed by the bidder and must be submitted to the BAC Secretariat, PITAHC Building, Matapang St., East Avenue Medical Center Compound, Barangay Central, Quezon City or sent thru fax at (02) 8376-3067 or email at bacpitahc@gmail.com. The proposal shall be received until 17 December 2021.
- 4. PITAHC reserves the right to waive any formality in the responses to the eligibility requirements and to this invitation. PITAHC further reserves the right to reject all proposals, or declare a failure of small value procurement, or not award the contract, and makes no assurance that the contract shall be entered into as a result of this invitation without thereby incurring any liability to the affected bidder or bidders in accordance with R.A. No. 9184 and its Implementing Rules and Regulations.
- 5. For any clarification, you may contact **Rodelio Mendez**, Jr. at telephone no. (02) 8376-3067

## (Sgd) DR. FRANCIS VICENTE S. RAS Chairperson, PITAHC BAC

PITAHC Building, Matapang Street, East Avenue Medical Center Compound, Barangay Central, Quezon City, Philippines Telefax: (632) 8376-3067 / 8376-3068 Trunklines: (632) 8282-5193 /8282-5194 Email Address: pitahc@gmail.com Website: www.pitahc.gov.ph



Republic of the Philippines Department of Health Philippine Institute of Traditional and Alternative Health Care (PITAHC)



# **TERMS AND CONDITIONS**

- 1. Bidders shall provide the correct and accurate information required in this form.
- 2. Delivery Schedule: Please refer to the Terms and Conditions Item X: Delivery Terms for each lot.
- 3. Delivery Site: PITAHC CENTRAL OFFICE, East Avenue Medical Center Compound, Matapang St., Brgy. Central, Quezon City
- 4. Payment Term: 100% full payment shall be made within **Thirty (30) calendar days** after the date of final inspection and acceptance or issuance of Certificate of Completion. For items that require installation, testing and commissioning, the submission of As-built Plans, Letter of Request for Payment, and other necessary attachments are required.
- 5. Price proposal must be valid for a period of thirty (30) calendar days from the date of submission.
- 6. Price proposal to be denominated in **Philippine Peso**, include all taxes and duties and/or levies payable.
- 7. Proposals exceeding the ABC shall be automatically rejected.
- 8. The **award of contract** shall be made to the lowest calculated and responsive proposal which complied with the minimum technical specifications and other terms and conditions stated herein.
- 9. Any interlineations, erasures, or overwriting shall be valid only if they are signed or initialed by the bidder or any of his/her duly authorized representative/s.
- 10. Liquidated damages equivalent to one tenth of one percent (0.001%) of the value of the goods not delivered within the prescribed delivery period shall be imposed per day of delay. PITAHC shall rescind the contract once the cumulative amount of liquidated damages reaches ten percent (10%) of the amount of the contract, without prejudice to other courses of action and remedies open.
- 11. The bidder must **submit a copy** of the following documents, **together with the proposals**, to ensure that the said bidder is technically, legally and financially capable to undertake the proposed project:
  - Valid and current Mayor's/Business Permit
  - Business/Income Tax Return for CY 2019/2020
  - Notarized Omnibus Sworn Statement by the prospective bidder in the new prescribed form as per GPPB Resolution No. 16-2020
  - PHILGEPS Registration Number (to be indicated in the Price Proposal Form)





Annex "A"

# TERMS AND CONDITIONS

## SUPPLY, DELIVERY, INSTALLATION, TESTING, AND COMMISSIONING OF VARIOUS REQUIREMENTS FOR THE PITAHC CENTRAL OFFICE LABORATORY

# I. BACKGROUND

In September 2012, the Governance Commission for Government-Owned and Controlled Corporations (GCG) re-classified the Philippine Institute of Traditional and Alternative Health Care (PITAHC) as a research institution. As such, PITAHC is mandated to encourage scientific research on and develop traditional and alternative health care that have direct impact on public health care.

In carrying-out its mandate, PITAHC through its Research and Development Division commissioned the Healthcare Practice and Policy Management, Inc. (HPPMI) as a technical consultant to conduct the feasibility study on the proposed PITAHC Central Office Laboratory towards enhanced research and development capacity on Traditional and Complementary Medicine (T&CM) in the country. Based on the submitted final report of HPPMI, the bidding for the construction of the PITAHC Central Office Laboratory was conducted, and the infrastructure project has been awarded.

In view of this, the fixture and equipment as well as the laboratory supplies for the Central Office laboratory have to be procured as these require to be systematically integrated to the construction of the laboratory. This Terms and Conditions provides the detailed information for the various requirements for the PITAHC Central Office Laboratory.

## II. APPROVED BUDGET

The approved budget for this procurement is Six Hundred Twenty-Four Thousand Five Hundred Eighty Pesos (PHP 624,580.00).

#### III. GENERAL CONDITION

# A. SUMMARY OF SERVICES

The Supplier/s is/are required to supply, deliver, install, test, and commission the items and facilities indicated in the following works:

# LOT 1

- Supply, Delivery, Installation, Testing, and Commissioning of 1.5 HP Split-Type Wall Mounted Air Conditioning Units; and
- Supply, Delivery, Installation, Testing, and Commissioning of 2.0 HP Split-Type Wall Mounted Air Conditioning Units.

Page 1 of 12





# LOT 2

- Supply Delivery, Installation, and Testing of 2x28W LED Louver Housing, Recessed Lighting Fixture;
- Supply, Delivery, Installation, Testing, and Commissioning of Exhaust Fans with Ducting; and
- 3. Supply, Delivery, Installation, and Testing of LED Emergency Lights.

# LOT 3

- 1. Supply, Delivery, Installation, Testing, and Commissioning of Smoke Detectors;
- 2. Supply and Delivery of Room Thermometers;
- 3. Supply and Delivery of Fire Extinguishers; and
- 4. Supply and Delivery of Waste Bins.

# B. INSPECTION OF SITE

- As part of the procurement requirement, the prospective Supplier/s shall conduct a site inspection and secure a Certificate of Site Inspection, which shall be issued by the PITAHC Project Engineer. The said certificate, which shall be submitted as part of the technical proposal, shall be issued specifically for the lot/s with items that require installation, testing, and commissioning.
- The Winning Supplier/s shall inspect the site premises to consider all the conditions that may directly or indirectly affect the works, measure any existing work, and verify all the given dimensions.

## C. TECHNICAL SPECIFICATIONS PER LOT

LOT 1

1.1 Supply, Delivery, Installation, Testing, and Commissioning of 1.5 HP Split-Type Wall Mounted Air Conditioning Units:

| Specifications                        |   |                               |
|---------------------------------------|---|-------------------------------|
| <ul> <li>Type</li> </ul>              | : | Inverter                      |
| <ul> <li>Power Supply</li> </ul>      | : | 1Ph 230V - 60Hz               |
| <ul> <li>Cooling Capacity</li> </ul>  | : | 12,960 (3,312 - 14,760) KJ/hr |
| <ul> <li>Power Input</li> </ul>       | : | 1080 (210 - 1,330) W          |
| <ul> <li>Energy Efficiency</li> </ul> | : | 12.0 (15.8 - 11.1) KJ/W-hr    |

Page 2 of 12





| Ratio   |   |  |
|---|---|--|
| <ul> <li>Sound Level Low</li> </ul>                         | : | 23 dB(A)                                     |
| <ul> <li>Refrigerant</li> </ul>                             | : | R32  |
| Quantitize and  | : | HPLC Area – 2 units                          |
| <ul> <li>Quantities and<br/>Identified Locations</li> </ul> |   | Proposed Positive Pressure Room - 2<br>units |
| <ul> <li>Warranty</li> </ul>                                | : | Minimum of 1 year                            |

# 1.2 Supply, Delivery, Installation, Testing, and Commissioning of 2.0 HP Split-Type Wall Mounted Air Conditioning Units:

| pecifications   |   | 2   |
|---|---|---|
| • Туре  |   | Inverter  |
| <ul> <li>Power Supply</li> </ul>                            |   | 1Ph 230V - 60Hz   |
| <ul> <li>Cooling Capacity</li> </ul>                        | : | 16,560 (2,988 - 18,000) KJ/hr   |
| <ul> <li>Power Input</li> </ul>                             | : | 1,425 (230 - 1,725) W   |
| <ul> <li>Energy Efficiency<br/>Ratio</li> </ul>             |   | 11.6 (13.0 - 10.4) KJ/W-hr  |
| <ul> <li>Sound Level Low</li> </ul>                         | : | 24 dB(A)  |
| <ul> <li>Refrigerant</li> </ul>                             | : | R32   |
|   | : | Extraction Area – 2 units   |
| <ul> <li>Quantities and<br/>Identified Locations</li> </ul> | : | Central Laboratory – 3 units (The<br>existing air conditioning units will be<br>relocated.) |
| <ul> <li>Warranty</li> </ul>                                | : | Minimum of 1 year   |

# LOT 2

2.1 Supply Delivery, Installation, and Testing of 2x28W LED Louver Housing, Recessed Lighting Fixtures:

| Specifications                        |   |                          |  |
|---------------------------------------|---|--------------------------|--|
| <ul> <li>No. of Lamp</li> </ul>       |   | 2 pieces                 |  |
| <ul> <li>Material</li> </ul>          | : | Metal Sheet Housing      |  |
| <ul> <li>Reflector</li> </ul>         | : | Mirrored Reflector       |  |
| <ul> <li>Mounting</li> </ul>          | : | Recessed Mount           |  |
| <ul> <li>Wiring Connection</li> </ul> |   | Double End               |  |
| <ul> <li>Light Compatible</li> </ul>  | : | T8 Tube Lights           |  |
| <ul> <li>Quantities and</li> </ul>    | : | Extraction Area – 6 sets |  |

Page 3 of 12





| Identified Locations | : | HPLC Area – 3 sets                          |
|----------------------|---|---|
|                      | : | Central Laboratory – 8 sets                 |
|                      | : | Anteroom - 1 set                            |
|                      |   | Proposed Positive Pressure Room - 6<br>sets |
|                      | : | Storage Room – 3 sets                       |
| Warranty             | : | Minimum of 1 year                           |

2.2 Supply, Delivery, Installation, Testing, and Commissioning of Exhaust Fans with Ducting

| <ul> <li>Range</li> </ul>                                   | : | Airflow   |
|---|---|---|
| <ul> <li>Operational Voltage</li> </ul>                     | : | 220 - 240 V   |
| <ul> <li>IP Degree of<br/>Protection</li> </ul>             |   | To be determined, in coordination with<br>Research and Development Division |
| <ul> <li>Power Consumption</li> </ul>                       |   | >35 W   |
|   | : | Epoxy coated steel  |
| <ul> <li>Canopy Hood</li> </ul>                             | : | For the Atomic Absorption<br>Spectrometer (AAS) and Fume Hood               |
| -   | : | Extraction Area - 1 set   |
| <ul> <li>Quantities and<br/>Identified Locations</li> </ul> | : | HPLC Area - 1 set   |
| Identified Eductions  | : | Central Laboratory – 1 set  |
| <ul> <li>Warranty</li> </ul>                                | : | Minimum of 1 year   |

2.3 Supply, Delivery, Installation, and Testing of LED Emergency Light

| <ul> <li>Energy Efficiency<br/>Label</li> </ul> | : | LED  |
|---|---|--|
| <ul> <li>Performance Time</li> </ul>            | : | >6 hours   |
| <ul> <li>Charging Time</li> </ul>               |   | <20 hours, with overcharge and<br>discharge protection |
| Power   | : | 220 - 240 V  |
| Wall Mounted                                    |   |  |
| <ul> <li>Warranty</li> </ul>                    | : | Minimum of 1 year                                      |
| Quantities and                                  | : | Extraction Area - 1 unit                               |
| Identified Locations                            | : | HPLC Area – 1 unit                                     |

Page 4 of 12





| : | Central Laboratory – 1 unit                 |
|---|---|
| : | Anteroom – 1 unit                           |
|   | Proposed Positive Pressure Room - 1<br>unit |
| : | Storage Room – 1 unit                       |

# LOT 3

# 3.1 Supply, Delivery, Installation, Testing, and Commissioning of Smoke Detectors

| Specifications  |   |  |
|---|---|--|
| <ul> <li>Type</li> </ul>                                    | : | Battery Operated   |
| <ul> <li>Alarm Volume</li> </ul>                            | : | >84dB  |
| <ul> <li>Operating<br/>Temperature</li> </ul>               | : | 0° C - 50° C   |
| <ul> <li>Addressable</li> <li>Detector</li> </ul>           | : | Detectors communicate within<br>networked detection system |
| <ul> <li>Visual Alarm<br/>Indicator</li> </ul>              |   | LED  |
| <ul> <li>Standard</li> </ul>                                | : | LPCB certified   |
| <ul> <li>Warranty</li> </ul>                                | : | Minimum of 1 year  |
|   | : | Extraction Area - 2 sets                                   |
|   | : | HPLC Area – 2 sets   |
| <ul> <li>Quantities and<br/>Identified Locations</li> </ul> | : | Central Laboratory - 2 sets                                |
| Identified Locations  | : | Anteroom – 1 set   |
|   | : | Proposed Positive Pressure Room - 2 sets                   |
|   | : | Storage Room – 1 set                                       |

# 3.2 Supply and Delivery of Room Thermometers

| pecifications                | _    |   |
|------------------------------|------|---|
| <ul> <li>Accuracy</li> </ul> |      | ±2% RH and ±0.5° F, with manual<br>calibration option |
| Temperature Range            | :    | -58° F to 158° F (-50° C - 70° C)                     |
| <ul> <li>Display</li> </ul>  | :    | Digital   |
| Humidity and Tempe           | rati | ure Indicator   |
| Warranty                     | :    | Minimum of 1 year                                     |
| Quantities and               | :    | Extraction Area – 1 piece                             |

Page 5 of 12





| Identified Locations | : | HPLC Area - 1 piece                          |
|----------------------|---|--|
|                      | : | Central Laboratory – 1 piece                 |
|                      | : | Anteroom - 1 piece                           |
|                      |   | Proposed Positive Pressure Room - 1<br>piece |
|                      | : | Storage Room – 1 piece                       |

# 3.3 Supply and Delivery of Fire Extinguishers

| Specifications  |   |  |  |  |
|---|---|--|--|--|
| <ul> <li>Chemical Contents</li> </ul>                       | : | Monoammonium Phosphate                     |  |  |
| Class   | : | ABC  |  |  |
| <ul> <li>Capacity</li> </ul>                                | : | >3 kg                                      |  |  |
| <ul> <li>Test Pressure</li> </ul>                           | : | >2.5 MPa                                   |  |  |
| <ul> <li>Working Pressure</li> </ul>                        | : | >1344 kPa at 28° C                         |  |  |
| <ul> <li>Discharge Range</li> </ul>                         | : | 3 meters                                   |  |  |
| <ul> <li>Discharge Time</li> </ul>                          | : | Less than 10 seconds                       |  |  |
| <ul> <li>Working Temperature</li> </ul>                     |   | -20° C to +60° C                           |  |  |
| <ul> <li>Mounting Bracket include</li> </ul>                | d |  |  |  |
| <ul> <li>Warranty</li> </ul>                                |   | 3 months                                   |  |  |
|   | : | Extraction Area - 1 piece                  |  |  |
|   | : | HPLC Area - 1 piece                        |  |  |
| Our stiller and Identified                                  | : | Central Laboratory - 1 piece               |  |  |
| <ul> <li>Quantities and Identified<br/>Locations</li> </ul> | : | Anteroom – 1 piece                         |  |  |
| 200000  | : | Proposed Positive Pressure Room<br>1 piece |  |  |
|   | : | Storage Room – 1 piece                     |  |  |

3.4 Supply and Delivery of Waste Bins

| Specifications                |   |  |  |  |  |
|-------------------------------|---|--|--|--|--|
| <ul> <li>Material</li> </ul>  | : High Density Polyethylene                                       |  |  |  |  |
| <ul> <li>Capacity</li> </ul>  | : >80 liters  |  |  |  |  |
| <ul> <li>Dimension</li> </ul> | : (Manufacturer's Standard)                                       |  |  |  |  |
| Color                         | To be determined, in accordance to the internal collection system |  |  |  |  |
| Others                        | : Tight lid to prevent spread of odor,<br>bacteria                |  |  |  |  |

Page 6 of 12





|   | : | With pedal system       |
|---|---|-------------------------|
|   | : | Wheels                  |
| <ul> <li>Quantities and<br/>Identified Locations</li> </ul> | : | Anteroom - 2 pieces     |
|   | : | Storage Room – 3 pieces |

# D. PROTECTION OF WORK AND PROPERTY

For items that require installation, testing, and commissioning, the Supplier/s shall protect the work and property by:

- Providing watchmen to guard the site and its premises throughout the duration of the project including during work suspension or time extensions;
- 2. Providing site protections, board up, and signs for the installation;
- Replacing the work damaged due to failure to provide protection, without cost to PITAHC;
- Leaving the premises clean, neat and orderly, and removing stains, spots, blemishes and other dirt from the finished work;
- 5. For the storage of materials:
  - a. Stacking of all tools and materials in a stable and self-supporting manner, and removing all nails and sharp objects on all reusable lumber before storage; and
  - Removing dust-producing materials from the project site as directed by PITAHC;
- Keep all access ways including stairways and passageways, free from obstructions and installation materials at all times;
- Taking due care to protect the existing structures which may be affected by the work to be implemented; and
- Thoroughly cleaning the project site including all areas disturbed by installation, testing, and commissioning activities.

# E. WORKMANSHIP

For items that require installation, testing, and commissioning, the Supplier/s shall protect the work and property by:

 The workforce shall consist of skilled and competent workers who regularly engage or specialize in their respective fields of work (Must be in service or line of business for at least 3 years).

Page 7 of 12





- Workmanship at all phases of work shall be of the very best of trade. All installations shall conform to the provisions of the National Building Code of the Philippines (PD 1096), Electrical Engineering Law (RA 7920), Mechanical Engineering Law (RA 5336), Plumbing Code (RA 1378), Fire Code (RA 9514), and other laws covering ordinances and regulations.
- Any additional expense incurred during installation must be shouldered by the Supplier/s. The Supplier/s shall include extra installation costs it may incur in their Price Bid Form.
- Constant coordination between the Supplier/s and the PITAHC Project Engineer shall be ensured.

# F. SAFETY REQUIREMENTS

In order to ensure the safety of its personnel, for items that require installation, testing, and commissioning, the Supplier/s shall:

- Ensure that the standard safety procedures, minimum public health standards prescribed by the Department of Health (DOH), and such related protocols or guidelines issued by the appropriate government agencies shall be applied and complied with;
- Ensure that the workers are in proper safety attire/uniform and shall be worn at all times while in the building premises;
- Ensure the safety of its personnel as well as the PITAHC personnel for the duration of the installation, and that first aid kits are available at the site;
- In the event that a personnel/worker manifests any symptom of COVID-19, he/she shall be prohibited from entering the PITAHC building, and shall be replaced by another personnel/worker.

# G. PROHIBITIONS

The following are prohibited acts inside the PITAHC building, premises, work and storage areas for the duration/delivery of the project/item/s:

- 1. Smoking;
- 2. Drinking alcoholic beverages;
- 3. Using illegal drugs and other prohibited substances;
- 4. Gambling of any type;

Page 8 of 12



Philippine Institute of Traditional and Alternative Health Care (PITAHC)



- 5. Carrying items determined by PITAHC as "deadly instruments";
- 6. Sleeping in the project site;
- 7. Having meals and/or snacks within the project work areas; and
- Using the elevator unnecessarily except when transporting installation materials to the project areas or in case of emergency.

## H. PROJECT COORDINATION AND SUPERVISION

For items that require installation, testing, and commissioning, the Supplier/s is/are responsible for:

- Coordinating the various parts of the trades of work including any approved subcontracted work; and
- 2. Employing competent professionals and laborers to oversee the installation work.

#### I. SUBMITTALS

The Supplier/s shall be required to submit:

- 1. A list of materials needed for installation, testing, and commissioning;
- The catalogue or manual from the manufacturer and/or dealer, indicating the specifications of items installed, tested, and commissioned;
- 3. The following for approval by the PITAHC Project Engineer:
  - a) Shop drawings for all work requiring fabrication; and
  - b) Mock-ups of fabricated item.

## IV. CLOSE-OUT

The Supplier/s shall submit as-built plans of items installed, tested, and commissioned, duly signed and sealed by the concerned trade professionals in three (3) sets of reproducible A3 size copies. The electronic copy of the as-built plans shall also be submitted.

## V. LAYOUT, MARKINGS AND ELEVATIONS

For items that require installation, testing, and commissioning, the Supplier/s shall:

1. Indicate the layout of electrical, mechanical, ventilation, and plumbing connections; and

Page 9 of 12





Establish floor and wall elevations with corresponding markings for approval by the PITAHC Project Engineer before any fabricated items are installed.

## VI. FORMWORKS AND SCAFFOLDING

The Supplier/s shall supply and install sufficient forms, scaffoldings, bracings and staging, if applicable.

# VII. ARCHITECTURAL WORKS

Whenever applicable, for items that require installation, testing, and commissioning, the Supplier/s is/are responsible for:

#### A. PAINTING WORKS

- Painting of all surfaces wood, plastered walls and soffits, cement boards as indicated in the plans;
- 2. Application of skim coat to all masonry and concrete surfaces to be painted;
- 3. Application of two-coat red lead primer to all steel and metal surfaces;
- Color selection of surfaces shall be approved by the PITAHC Project Engineer prior to painting; and
- 5. All painting works in accordance with the plans and specifications.

# B. SPECIAL CONSTRUCTION

Construction of all steel and aluminum works in accordance with the best practices of the steel and aluminum industry.

# VIII. ELECTRICAL, MECHANICAL, VENTILATION, AND PLUMBING WORKS

For items that require installation, testing, and commissioning, the Supplier/s shall:

- 1. Provide and tap the system conforming to the aforementioned provisions;
- Follow the plans, specifications and scope of works to complete the project and render it to be operational;
- Furnish and install other supporting materials and equipment deemed necessary to complete the project; and

Page 10 of 12





 Conduct testing and commissioning for the air-conditioning units, exhaust fans, and smoke detectors.

# IX. CONSTRUCTION CLEARANCES

The Supplier/s shall secure from the PITAHC Project Engineer the following clearances prior to commencing the requisite work for items that require installation, testing, and commissioning:

- Plumbing fixtures, accessory installation clearance verification of location and adherence to design specifications of plumbing roughing-ins;
- Electrical fixture, device, equipment installation clearance verification of location and adherence to design specifications of electrical roughing-ins; and
- Mechanical fixture, device, equipment installation clearance verification of location and adherence to design specifications of mechanical roughing-ins.

# X. DELIVERY TERMS

| Lot Number and Scope of Works   | Completion Schedule   |  |  |  |
|---|---|--|--|--|
| Lot 1   | Fifteen (15) working days from the  |  |  |  |
| 1. Supply, Delivery, Installation, Testing, and   | date of receipt of Notice to Proceed.                                       |  |  |  |
| Commissioning of 1.5 HP Split-Type Wall   | The Notice to Proceed shall be issued                                       |  |  |  |
| Mounted Air-Conditioning Units; and   | to the Supplier/s after the completion                                      |  |  |  |
| 2. Supply, Delivery, Installation, Testing, and   | of the prerequisite construction  |  |  |  |
| Commissioning of 1.5 HP Split-Type Wall   | works as determined by the PITAHC   |  |  |  |
| Mounted Air-Conditioning Units  | Project Engineer.   |  |  |  |
| Lot 2   |   |  |  |  |
| <ol> <li>Supply, Delivery, Installation, and Testing<br/>of 2X28W LED Louver Housing, Recessed<br/>Lighting Fixture;</li> </ol> | Fifteen (15) working days from the<br>date of receipt of Notice to Proceed. |  |  |  |
| <ol> <li>Supply, Delivery, Installation, Testing, and</li></ol>   | The Notice to Proceed shall be issued                                       |  |  |  |
| Commissioning of Exhaust Fans with  | to the Supplier/s after the completion                                      |  |  |  |
| Ducting; and  | of the prerequisite construction works                                      |  |  |  |
| 3. Supply, Delivery, Installation, Testing, and   | as determined by the PITAHC Project   |  |  |  |
| of LED Emergency Lights   | Engineer.   |  |  |  |
| Lot 3   |   |  |  |  |
| <ol> <li>Supply, Delivery, Installation, Testing, and</li></ol>   | Fifteen (15) working days from the  |  |  |  |
| Commissioning of Smoke Detectors;   | date of receipt of Notice to Proceed.                                       |  |  |  |

Page 11 of 12



HISTITUTE OF REGISTER

 Supply and Delivery of Room Thermometers;
 Supply and Delivery of Fire Extinguishers; and
 Supply and Delivery of Waste Bins
 The Notice to Proceed shall be issued to the Supplier/s after the completion of the prerequisite construction works as determined by the PITAHC Project Engineer.

## XI. PAYMENT TERMS

100% full payment shall be made within thirty (30) calendar days after the date of Final Inspection and Acceptance or issuance of Certificate of Completion. For items that require installation, testing, and commissioning, the submission of As-built Plans, Letter of Request for Payment, and other necessary attachments is required.

# XII. LIQUIDATED DAMAGES

If the Supplier/s refuse/s or fail/s to satisfactorily complete the work within the specified contract time, plus any extension time duly approved, the Supplier/s shall pay PITAHC for liquidated damages, and not by way of penalty, an amount equal to one-tenth (1/10) of the one percent (1%) of the cost of the unperformed portion for every day of delay. The maximum deduction shall be ten percent (10%) of the amount of the contract.

#### XIII. RESERVATION CLAUSE

PITAHC reserves the right to reject any and all bids, declare a failure of bidding, or not to award the contract at any time prior to awarding, in accordance with Section 41 of the 2016 Revised Implementing Rules and Regulations (IRR) of Republic Act No. 9184, without incurring any liability to the affected bidders.





# PRICE PROPOSAL FORM

Date:

# The Bids and Awards Committee

PITAHC Building, Matapang Street, East Avenue Medical Center Compound, Barangay Central Quezon City

Sir/Madam:

After having carefully read and accepted the Terms and Conditions, I/we submit our proposal for the item as follows:

| Lot<br>No. | Item Description   | Qty | UOM   | Installation | Total<br>Price<br>In PhP | Total Price<br>(VAT<br>inclusive) | Compliance<br>to Technical<br>Specification |    |
|------------|--|-----|-------|--------------|--------------------------|-----------------------------------|---|----|
| 1          | Supply, Delivery, Installation, Testing,<br>and Commissioning of 1.5 HP<br>Split-Type Wall Mounted Air<br>Conditioning Units<br>(Please see Annex "A" for the detailed<br>Technical Specifications)                  | 4   | unit  | Cost         |                          | In PhP                            | Yes   | No |
|            | Supply, Delivery, Installation,<br>Testing, and Commissioning of 2.0<br>HP Split-Type Wall Mounted Air<br>Conditioning Units:<br>(Please see Annex "A" for the detailed<br>Technical Specifications)                 | 5   | unit  |              |                          |                                   |   |    |
| 2          | <b>Supply Delivery, Installation, and</b><br><b>Testing of 2x28W LED Louver</b><br><b>Housing, Recessed Lighting Fixtures</b><br>( <i>Please see Annex "A" for the detailed</i><br><i>Technical Specifications</i> ) | 27  | set   |              |                          |                                   |   |    |
|            | Supply, Delivery, Installation,<br>Testing, and Commissioning of<br>Exhaust Fans with Ducting<br>(Please see Annex "A" for the detailed<br>Technical Specifications)   | 3   | set   |              |                          |                                   |   |    |
|            | <b>Supply, Delivery, Installation, and</b><br><b>Testing of LED Emergency Light</b><br>(Please see Annex "A" for the detailed<br>Technical Specifications)   | 6   | unit  |              |                          |                                   |   |    |
| 3          | Supply, Delivery, Installation,<br>Testing, and Commissioning of<br>Smoke Detectors<br>(Please see Annex "A" for the detailed<br>Technical Specifications)   | 10  | set   |              |                          |                                   |   |    |
|            | <b>Supply and Delivery of Room</b><br><b>Thermometers</b><br>(Please see Annex "A" for the detailed<br>Technical Specifications)   | 6   | piece |              |                          |                                   |   |    |
|            | Supply and Delivery of Fire<br>Extinguishers<br>(Please see Annex "A" for the detailed<br>Technical Specifications)  | 6   | piece |              |                          |                                   |   |    |
|            | <b>Supply and Delivery of Waste Bins</b><br>(Please see Annex "A" for the detailed<br>Technical Specifications)  | 5   | piece |              |                          |                                   |   |    |

PITAHC Building, Matapang Street, East Avenue Medical Center Compound, Barangay Central, Quezon City, Philippines Telefax: (632) 8376-3067 / 8376-3068 Trunklines: (632) 8282-5193 /8282-5194 Email Address: pitahc@gmail.com Website: www.pitahc.gov.ph





Amount in Words:

Contact Number

| Lot I               |   |
|---------------------|---|
| Lot 2               |   |
| Lot 3               |   |
|                     |   |
|                     |   |
| The above-quoted pr | rice is inclusive of <b>all costs</b> and applicable taxes. |
| Very truly yours,   |   |
| Signature           | :   |
| Printed Name        | :   |
| Date                | :   |
| Company Name        | :   |

PHILGEPS Registration Number:\_\_\_\_\_

:

PITAHC Building, Matapang Street, East Avenue Medical Center Compound, Barangay Central, Quezon City, Philippines Telefax: (632) 8376-3067 / 8376-3068 Trunklines: (632) 8282-5193 /8282-5194 Email Address: pitahc@gmail.com Website: www.pitahc.gov.ph